



Prototype to Production

The Evolution of the SolidGround GIC Blocker

Presented by: Mike Londo, Consultant-Transmission Reliability Administrator – American Transmission Company, LLC April 8, 2015

Project Director: David Wojtczak, Team Leader Substation Services
In coordination with: ABB Automation and Power World

Helping to **keep the lights on,**
businesses running and communities strong®



In the news



The screenshot shows a news article from the Swinburne University of Technology Media Centre. The header includes the university's logo and name. The article title is "Huge solar storms to hit Earth this weekend" and it was posted on Friday, September 12, 2014. The breadcrumb trail indicates the article is in the "In the News" section for the month of September 2014. A share button is visible in the top right corner of the article preview.

SWINBURNE UNIVERSITY OF TECHNOLOGY


Media Centre

Media Centre > In the News > 2014 > September > Huge solar storms to hit Earth this weekend

SHARE

Huge solar storms to hit Earth this weekend

Date posted: Fri 12 Sep 2014



- There will be disruption to radio, TV and satellite signals, with possible degradation of GPS tracking accuracy and even electrical power line fluctuations.

Objective

Show how ATC and EMPrimus/ABB worked together to take the SolidGround unit from Prototype to Production.




Presentation Overview

- Conceptual design
- Critical development
- Construction deployment

Conceptual Design

Design Principles


- Block GIC using a capacitor
- Protect transformer N-G with an arrester
- Control with a PLC



Conceptual Design

Delivered Product

- ❑ Bypass switch
- ❑ Smaller symmetrical footprint
- ❑ CTs added



Critical Development

The Team


- Cross Functional
 - Back Office (Ops, Asset Mgt, Eng., PM, SP&C)
 - Field (Commissioning, Constr.)
 - Mix (Maintenance, M&C, EMPrimus/ABB)
- Synergistic
 - Mutual respect
 - Listening to understand
 - Breakthroughs



Critical Development

The Transformation

- Fail Safe Resilience
 - Spark Gap
 - Non consumable
 - Repeatable
 - Rogowski Coil (N-G path proof)



Critical Development

The Transformation (cont'd)

- Fault Tolerant Operation
 - Automatic
 - Status and alarms




Construction Deployment

- Site Preparation
 - Placement of the unit
 - Connections
 - Neutral (X0 to unit)
 - Grounds (to ground grid)
 - Control (to CH)



Construction Deployment

- System Integration
 - Strategic location
 - Operational
 - Maintainable



Date	Time	Description	Local	Name
01/28/2015	14:57:21.185	R1 / R2 in Supervisory (SEL-451 OUT213)	Local	R1 R2
01/28/2015	14:57:46.057	R1	Open	SMPIC
01/28/2015	14:57:46.057	R1 43L/S	Local	SMPIC
01/28/2015	15:18:43.638	T1 NID DC Breaker Open	Open	SMPIC
01/28/2015	15:20:00.672	T1 NID Maintenance Switch to NID	Open	SMPIC
01/28/2015	15:32:19.322	T1 NID CT1 Loss Of Transformer Neutral	Alarm	T1 NI
01/28/2015	15:39:32.291	T1 NID Maintenance Switch to Ground	Closed	SMPIC
01/28/2015	15:45:29.379	T1_NID Enable / Disable	Disable	SMPIC

Questions?

David Wojtczak
Team Leader, Substation Services
(262)-506-6823

dwojtczak@atcllc.com

Mike Londo
Transmission Reliability Administrator
Real-Time Operations
mlondo@atcllc.com